



# CERTIFICATE OF ACCREDITATION

## The ANSI National Accreditation Board

Hereby attests that

**Zero/Six Consulting, LLC**  
1027 Tremont Street  
Galveston, TX 77550

Fulfils the requirements of

**ISO/IEC 17025:2017**

In the field of

**TESTING**

This certificate is valid only when accompanied by a current scope of accreditation document.

The current scope of accreditation can be verified at [www.anab.org](http://www.anab.org).

Jason Stine, Vice President

Expiry Date: 26 October 2026

Certificate Number: AT-2090



This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communiqué dated April 2017).

## SCOPE OF ACCREDITATION TO ISO/IEC 17025:2017

### Zero/Six Consulting, LLC

1027 Tremont Street  
Galveston, Texas 77550  
409 740 0090

William (Bill) H. Coltzer, Jr. [bcoltzer@z6consulting.com](mailto:bcoltzer@z6consulting.com)  
Lidija Bikova [LBikova@z6consulting.com](mailto:LBikova@z6consulting.com)  
Website: [www.z6consulting.com](http://www.z6consulting.com)

### TESTING

Valid to: **October 26, 2026**

Certificate Number: **AT-2090**

#### Construction Materials


Specific Tests and/or Properties Measured	Specification, Standard, Method, or Test Technique	Items, Materials or Product Tested	Key Equipment or Technology
Water infiltration	ASTM E 1105, ASTM E331, ASTM E547, AAMA 501,	Exterior Windows, Doors, Skylights, Curtain Walls	Water Distribution Rack, Centrifugal Blower, Manometer, Wind Generator, Spray Wand
Air Infiltration	ASTM E283, ASTM E783	Exterior Windows, Doors, Skylights, Curtain Walls	Centrifugal Blower, Laminar Flow Element, Manometer
Water and Air Infiltration	AAMA 502, AAMA 503	Exterior Windows, Doors, Skylights, Curtain Walls	Water Distribution Rack, Centrifugal Blower, Manometer
Deflection / Deglazing	ASTM E330 ASTM E1592	Exterior Windows, Doors, Skylights, Curtain Walls	Digital Deflection Indicator, Centrifugal Blower
Uplift Force	ASTM E907, FM Global 1-52	Roofing Systems	Uplift Chamber, Manometer, Centrifugal Blower
Roofing, Window Sealant, Foundation Humidity, Cladding Moisture Absorption	ASTM C1521, ASTM F2170, Rilem Commission 25/PEM test method 1154)	Miscellaneous	Sealant Test Kit, , in situ probes, Rilem Tubes
Whole Building Enclosure Airtightness Compliance	ASTM E779, ASTM E1186	Building and Home Enclosures	High Pressure Blower Door Systems, Smoke Tracer Unit, Infrared Camera
Pull-off Strength of Adhered weather Barrier	ABAA T0002-2019 ANSI/SPRI/FM MPO-1	Weather Barrier	Construction Load Cell Pull Tester

## Construction Materials

Specific Tests and/or Properties Measured	Specification, Standard, Method, or Test Technique	Items, Materials or Product Tested	Key Equipment or Technology
Electronic Methods for Detecting and Locating Leaks in Waterproof Membranes	D7877, ASTM D8231	Waterproof Membranes	High & Low Voltage Electronic Detection Units
Field Test Procedure for Determining Resistance of Roofing Fasteners	ANSI/SPRI-FX-1 2021	Roofing Fasteners	Construction Load Cell Pull Tester

Note:

1. This scope is formatted as part of a single document including Certificate of Accreditation No. AT-2090.



Jason Stine, Vice President

